



CONSTRUCT:		CONSTRUCT:	
100% L.S.	MAINTENANCE AND PROTECTION OF TRAFFIC	720 S.Y.	CONCRETE SIDEWALK, 4" THICK, 4' WIDE
60 M-HRS	POLICE TRAFFIC DIRECTORS	500 S.Y.	CONCRETE DRIVEWAY APRON, 6" THICK
4250 S.Y.	MILLING, 2" THICK	200 S.Y.	DRIVEWAY RESTORATION MIX I-5
460 TONS	BITUMINOUS CONCRETE SURFACE COURSE, 2" THICK, MIX I-5	5 UNIT	RESET MANHOLE CASTINGS
100 TONS	BITUMINOUS STABILIZED BASE COURSE, 4" THICK, MIX I-2	3 UNIT	RESET W.V.
2200 L.F.	GRANITE BLOCK CURB	1 UNIT	BICYCLE SAFE GRATES
100 S.Y.	D.G.A., 6" THICK	1 UNIT	INLET RISERS AS DIRECTED BY ENGINEER
100 L.F.	ROOF DRAINS (SDR 35)	5 UNIT	TYPE "B" INLET
		225 L.F.	15" R.C.P.
		1 UNIT	TREE REMOVAL OVER 12" TO 24" DIA
		8 UNIT	TREE REMOVAL OVER 24" TP 36" DIA
		100% L.S.	LANDSCAPE RESTORATION TO INCLUDE 4" THICK TOPSOIL, FERTILIZER, SEEDING TYPE "A" & STRAW MULCH

%%UGENERAL NOTES

- R.O.W. LINES, PROPERTY LINES AND LOT INFORMATION SHOWN ON THIS PLAN ARE BASED UPON BOROUGH OF MADISON TAX MAPS.
- ROADWAY AND ROADWAY UTILITIES ARE BASED UPON FIELD OBSERVATIONS PERFORMED BY THE BOROUGH OF MADISON ENGINEERING DEPARTMENT AND ARE APPROXIMATE IN LOCATION.

LOT 3 14 PAGE ST.	LOT 4 12 PAGE ST.	LOT 5 10 PAGE ST.	LOT 6 6 PAGE ST.	LOT 7 2 PAGE ST.
----------------------	----------------------	----------------------	---------------------	---------------------

LIMITS OF PROPOSED PAVEMENT EXIST. PAVEMENT TO BE SAWCUT

**ROSEMONT AVENUE
ROADWAY IMPROVEMENT
L B STA. 0+55 TO B STA. 11+35**

BOROUGH OF MADISON
DEPARTMENT OF ENGINEERING
HARTLEY DODGE MEMORIAL
MADISON, MORRIS COUNTY, N.J. 07940
(973) 593-3042

NO.	REVISIONS	DATE	BY	CHK.	APPR

ROBERT A. VOGEL, P.E.
PROFESSIONAL ENGINEER N.J. LIC. NO. 34463

SCALE:	1" = 30'
DATE:	4-15-02
DWG. FILE:	ROSE.DWG
DWG. NO.:	5 of 10